Analysis of prefabricated building system on construction quality and efficiency

Gang Bai

Guangdong Provincial Key Laboratory of Durability for Marine Civil Engineering, Shenzhen University, Shenzhen, Guangdong, 518060, China 15313502236@163.com

Keywords: Prefabricated building system; construction engineering quality; construction engineering efficiency

Abstract: This paper discusses the overview of the prefabricated building system, the impact on the quality and efficiency of construction engineering, and the future development trends. Firstly, the basic concepts and characteristics of prefabricated buildings are introduced, and its development process is reviewed. Then the classification and characteristics of prefabricated building system are classified and analyzed. The influence of prefabricated buildings on the quality of construction projects is mainly studied. The influence of prefabricated buildings on the efficiency of construction engineering and the advantages of resource conservation are discussed. The application and effect of prefabricated building system are summarized, and the technologies and strategies to meet the challenges are proposed. The development trend of prefabricated buildings in the future is discussed. Through the research of this paper, we can better understand the advantages and challenges of prefabricated building system, and provide reference and reference for the future development.

1. Introduction

As an emerging way of building, prefabricated building systems have great potential in improving quality and efficiency. The paper aims to discuss the influence of the prefabricated building system on the quality and efficiency of construction engineering and explore its future development trend. Through the research on classification and characteristics, quality management requirements, construction efficiency improvement and other aspects, we can better understand the advantages and challenges of prefabricated building system, and provide guidance and reference for the practice and development of related fields.

2. Overview of the prefabricated building system

2.1 The basic concepts and characteristics of prefabricated buildings

2.1.1 Basic concepts

Prefabricated building is a way in which building components are prefabricated in a factory and then transported to the site for assembly and installation. It adopts industrial production and standardized components design, through the convenient transportation, shortened construction cycle, environmental friendly and other characteristics, improve the efficiency and quality of construction, and has a strong flexibility and disassembly^[1]. Prefabricated building system has become an important development trend in the field of modern architecture, providing new solutions for sustainable building and efficient construction.

2.1.2. Features

Industrial production: the prefabricated building system adopts the factory production mode. Through the standardized and large-scale production process, the building components can be produced in a high-quality and efficient way, greatly shortening the construction cycle.

Component standardization: the components in prefabricated building systems are usually strictly designed and manufactured, with a high degree of standardization and standardization. This can not only improve the accuracy and consistency of construction, but also realize the exchange and reuse of components^[2].

Convenient transportation: Since the prefabricated building components can be transported after the factory prefabrication, they can be quickly and conveniently transported through various transportation modes such as road, railway and waterway. This effectively solves the logistics and traffic restrictions faced by the traditional building site construction.

Environmental friendly: prefabricated building systems can minimize environmental pollution to the construction site and reduce noise and dust generation. At the same time, due to the high utilization rate of materials in the factory production process, it can effectively reduce the consumption and waste of resources in construction.

Flexibility and disassembly: prefabricated building systems have strong flexibility and can be customized and designed according to different needs. In addition, prefabricated building components are usually detachable to be convenient for later maintenance and transformation.

2.2 Classification and characteristics of prefabricated building systems

2.2.1 Classification

Classification by component type: According to the type of components used in prefabricated buildings, they can be divided into wall system, floor system, roof system, column system, etc. Each component type has the corresponding characteristics and the scope of application.

Classification by structural form: according to the structural form of the prefabricated building, it can be divided into frame type, module type, flat plate type, silo type, etc. Different structural forms are suitable for different architectural requirements and design requirements.

According to the construction stage: according to the different stages of prefabricated buildings in the construction process, they can be divided into full assembly, semi-assembly and partial assembly. Full assembly means that the whole building is directly transported to the site for assembly after the factory is prefabricated, while semi-assembly and partial assembly means that part of the components are assembled on site^[3].

By material classification: according to the type of materials used in prefabricated buildings, it can be divided into steel structure prefabricated buildings, concrete structure prefabricated buildings, wood structure prefabricated buildings, etc. Different materials have different properties and a range of application.

Classification by application field: According to the application field of prefabricated buildings, they can be divided into residential prefabricated buildings, commercial prefabricated buildings, educational prefabricated buildings, etc. Different application fields also have different requirements and characteristics of prefabricated building systems.

2.2.2 Features

Factory production: the prefabricated building system adopts factory prefabrication and assembly methods, and most of the components are processed and assembled in the factory to ensure controllable quality, high accuracy, and improve production efficiency and save construction time^[4]. This factory production mode effectively avoids the possible unstable factors and human errors in the traditional site construction, enabling the prefabricated building system to be implemented with higher quality and efficiency, accelerate the construction progress and reduce the construction cost.

Standardization and modular design: The prefabricated building system advocates standardized and modular design. Through unified size, specifications and interface, the interchangeability and versatility of components are realized, facilitating assembly and rapid installation. This design concept enables different projects to share the same components, and can flexibly combine and adjust according to the needs, to achieve the purpose of rapid building and adapting to different building needs. At the same time, standardized and modular design is also conducive to later maintenance and transformation, convenient replacement and upgrading of components.

Reduce construction noise and pollution: Compared with traditional construction methods, most of the prefabricated building system is processed and assembled in the factory, reducing the generation of construction noise, dust and waste on site, and is more friendly to the surrounding environment and residents. This construction mode of low noise and low pollution is conducive to improving the working environment of the construction site, reducing the interference and influence on the surrounding residents, and also reducing the pollution of air and water resources.

Resource and energy saving: prefabricated building systems reduce the waste of materials, and save energy consumption due to the efficiency of factory production. In the production process of prefabricated components, the use of materials is more accurate, reducing waste, while factory production enables close coordination between various processes, reducing unnecessary energy consumption. This resource saving and energy saving characteristic is in line with the principle of sustainable development and is of great significance in the construction industry.

3. The impact of the prefabricated building system on the quality of the construction engineering

3.1 Requirements for quality management of prefabricated buildings

Prefabricated buildings have high requirements for quality management. It requires the components to meet the design requirements in the production process, have consistent quality standards and dimensional accuracy, protect the components from damage during the transportation process, and ensure the correct installation position and connection mode in the site assembly process. Meanwhile, the construction site should be strictly managed to ensure the coordination and smooth progress in the construction process to avoid errors and accidents. These requirements

guarantee the quality and reliability of prefabricated buildings.

3.2 Advantages and challenges of quality management of prefabricated buildings

3.2.1 Advantages

Factory production: Prefabricated building systems, prefabricated and assembled in factories, can achieve centralized quality control and management. Compared with traditional construction methods, factory production can reduce human error, improve the accuracy and consistency of components, and ensure controllable quality.

Standardized design and production: prefabricated building systems advocate standardization and modular design, making components interchangeability and universal. This standardized design and production can reduce design errors and construction defects and improve the quality of construction^[5].

Strict quality inspection and acceptance: the prefabricated building system needs to go through strict quality inspection and acceptance procedures to ensure that each component meets the relevant standards and requirements. These procedures include raw material testing, processing process monitoring, finished product inspection, etc., to effectively prevent defective products from entering the construction site.

3.2.2 Challenges

Construction environment restrictions: the prefabricated building system needs sufficient space and equipment for the processing and assembly of components, so the conditions of the construction site are higher. For some small or specially shaped sites, prefabricated buildings may not be implemented, limiting the scope of their application.

Technical requirements: prefabricated buildings require skilled workers and technicians to operate and manage. As prefabricated building systems are relatively new and have relatively few relevant technology and experience, training and attracting qualified personnel remains a challenge.

Adaptability of architectural design: the design of prefabricated building system needs to consider more about the size, interface and assembly mode of components. This may create new requirements for traditional architects to have the relevant knowledge and skills in prefabricated building design.

Lack of unity of quality supervision and standards: at present, prefabricated building quality supervision and related standards are not perfect, there are certain confusion and non-standard phenomenon. The lack of a unified quality supervision system and industry standards may lead to instability and consistency in quality control.

3.3. Key technologies and measures for the quality assurance of prefabricated buildings

Technical standards: Company formulate relevant technical standards for prefabricated buildings, clarify the requirements of component manufacturing, transportation and assembly, construction management and other aspects, and ensure that the quality conforms to the specifications. Through the formulation of unified technical standards, the design, manufacturing and construction process of the prefabricated building system can be standardized, the quality controllability and consistency can be improved, and the possibility of risks and problems can be reduced.

Process control: For the manufacturing process of parts, the staff need to take strict process control measures, including material selection, processing process, quality testing, etc., to ensure that the quality of parts meets the requirements. By optimizing the process flow and strengthening the process control and supervision, the errors and defects in the manufacturing process can be reduced, and the accuracy and quality stability of the components can be improved.

Quality testing: The staff needs to adopt a variety of quality testing methods, including material testing, component size accuracy test, structural strength test, etc., to ensure that the quality of components meets the design requirements. Through strict quality inspection, the problems in the manufacturing process of components can be found and corrected in time, and the safety and reliability of components can be guaranteed.

Construction management: Leaders need to fully manage the construction process of the prefabricated building, including the site organization, construction plan, quality control and safety management, to ensure the smooth progress of the construction. By establishing a scientific and effective construction management system, the construction efficiency and quality control level can be improved, and the problems and risks in the construction can be reduced.

Education and training: The company needs to provide professional technical training so that the personnel engaged in prefabricated construction construction can have the relevant knowledge and skills and be able to properly operate and use the prefabricated construction systems^[6]. Through education and training, the professional quality and skills of employees can be improved, and their quality awareness and responsibility can be enhanced to provide strong support for the quality management of prefabricated buildings.

Data management and traceability: Relevant departments need to establish a sound data management system to record and track all the links and processes of the prefabricated buildings, and ensure the traceability of quality and the timely handling of problems. Through data management and traceability, quality problems can be quickly located and solved, and lessons learned can be summarized to provide a basis for subsequent quality improvement.

Quality feedback and improvement: The department establishes the quality feedback mechanism, collects the quality problems and lessons encountered in the construction process in time, and makes continuous improvement and optimization. Through continuous quality feedback and improvement, the quality level of the prefabricated building system can be improved, the occurrence of quality problems can be reduced, and the overall construction quality can be continuously improved.

4. The impact of the prefabricated building system on the efficiency of the construction engineering

4.1 Impact of prefabricated buildings on project schedule management

Prefabricated buildings adopt factory prefabricated components and site assembly, which have higher construction efficiency and controllability compared with traditional construction methods. Through the application of modular design and standardized components, the construction period can be greatly shortened and the effect of project progress management can be improved. The factory production of prefabricated buildings can be carried out at the same time as the site construction, reducing the personnel demand and construction time of the construction team, and realizing the compression of the construction cycle. At the same time, the construction process of prefabricated buildings is more refined and standardized, which reduces the human factors and uncertainties in the site construction, and is conducive to the implementation of the plan in advance and the better control of the project progress.

4.2 Improvement of construction efficiency by prefabricated buildings

Prefabricated buildings use the prefabricated factory components, which can perform efficient, centralized and automated production in the factory environment, making the construction process

more rapid, accurate and consistent^[7]. Compared with traditional construction, the construction time of prefabricated buildings can be greatly shortened, and due to the standardization and reuse of components, the consumption of manpower and material resources in the construction process is reduced. In the construction process of prefabricated building system, by preparing and coordinating the production and transportation of each component in advance, the parallelization and rapid assembly of construction can be realized, further shortening the construction time. In addition, prefabricated buildings can be combined with other advanced technologies such as BIM (Building Information Modeling) to further improve construction efficiency and accuracy.

4.3 Advantages of prefabricated building system in resource saving

Prefabricated building system has high resource utilization efficiency and saving advantages. First, due to the use of prefabricated factory components, the amount of material needed can be accurately calculated, reducing waste. Secondly, the design and production of standardized components reduce the loss of materials and the generation of surplus materials. In addition, prefabricated buildings can also optimize the use of materials and energy consumption through intelligent design and construction management, and improve the overall efficiency of resource utilization. For example, in prefabricated building systems, energy-saving materials, intelligent control systems and other means can be used to reduce energy consumption. In general, the prefabricated building system can effectively save resources, reduce the environmental load, and meet the requirements of sustainable development.

5. Case analysis of prefabricated building practice

Case name: a high-rise residential project in Shenzhen

Background information: The project is located in Shenzhen city, which is a high-rise residential building. The prefabricated building system is used for construction, which is composed of multiple modular components.

Case analysis:

Improve project progress: The project uses prefabricated components such as prefabricated concrete wall panels and steel structure frame for production in the factory environment. This method of manufacturing before site assembly greatly improves the progress of the project, and the whole construction cycle is nearly one-third shorter than the traditional construction method.

Optimize construction efficiency: The modular design of prefabricated buildings makes the construction process more rapid and accurate. Each component is produced in the factory environment, the quality is controllable, and multiple construction tasks can be carried out at the same time, improving the construction efficiency. In addition, through the combination of BIM technology, the digital management of the construction process is realized, and the construction efficiency and quality are further improved.

Resource saving: prefabricated buildings use standardized components to reduce the waste of materials and surplus material generation. In addition, the consumption of materials and energy waste are reduced due to the repeated use of prefabricated components^[8]. By optimizing the design and construction management, resources are effectively saved and the environmental impact is reduced.

Improve quality control: prefabricated buildings can carry out comprehensive quality control in the production process of factory production, including material inspection, component size precision control, etc. This can ensure that the quality of the components meets the design requirements and improve the quality reliability of the overall project.

6. Advantages and challenges of prefabricated building systems

6.1 The advantages of the prefabricated building system

Shortening construction period: prefabricated buildings adopt prefabricated components and modular design, which can be produced and assembled in the factory environment, greatly shortening the construction period and improving the project progress. By preparing and coordinating the production and transportation of each component in advance, the parallelization and rapid assembly of construction can be realized.

Construction efficiency improvement: Due to the use of standardized components and automatic production methods in prefabricated buildings, the construction process is more rapid, accurate and standardized, and multiple construction tasks can be carried out at the same time, which improves the construction efficiency. The construction time of prefabricated buildings can be greatly shortened, and due to the standardization and reuse of components, the amount of manpower and material resources consumed in the construction process is reduced.

Resource conservation: prefabricated buildings realize the effective utilization and conservation of resources by accurately calculating material demand, reducing waste and waste production, and reuse prefabricated components. The use of prefabricated components can accurately calculate the amount of materials required and reduce waste; secondly, the design and production of standardized components reduce the loss of materials and waste materials.

Quality control: the production and quality inspection of prefabricated buildings in the factory environment can achieve comprehensive quality control, ensure that the quality of components meets the design requirements, and improve the quality and reliability of the overall project. Through the modular design and the application of standardized components, the consistency and stability of engineering quality can be greatly improved.

Environmental friendly: Through optimizing the design and construction management, the prefabricated buildings reduce the impact on the environment, reduce the construction noise, dust and waste emissions, and meet the requirements of sustainable development. Prefabricated building systems can effectively save resources, reduce environmental loads, and promote the green development of the construction industry.

Space flexibility: prefabricated buildings use modular components, which can be combined and disassembled according to the needs, providing greater spatial flexibility to meet the building needs of different functions and uses. The application of modular components makes the renovation and expansion of the building more flexible and convenient, and meets the personalized design of different space needs.

6.2 Challenges facing prefabricated building systems

Technical standards and specifications: At present, the technical standards and specifications of prefabricated buildings are not perfect enough, and they need to be further formulated and unified to ensure the quality control and construction safety. The formulation of unified technical standards and specifications can improve the design, production and construction level of prefabricated building system, and ensure the quality and safety of buildings.

Marketing and recognition: Compared with traditional construction methods, there is still a big gap in the marketing and recognition of prefabricated buildings, which needs to strengthen publicity and education to improve the social acceptance and recognition of prefabricated buildings. By increasing publicity, the company improves the visibility of prefabricated buildings and promotes their wide application in the market.

Cost control: The initial investment cost of prefabricated buildings is relatively high, including

equipment, process and personnel training. Therefore, how to reduce the cost and improve the economic benefits is a key problem^[9]. Technological innovation and economies of scale are needed to reduce the cost of prefabricated building systems and improve their competitiveness.

Design flexibility: Although prefabricated buildings have spatial flexibility, they still face some limitations in the design, which need to balance the innovation of design with the feasibility of construction, so as to realize the effective combination of design and actual construction. Further research and exploration of the design methods and techniques of prefabricated building systems are needed to improve their design flexibility and applicability.

7. Technologies and strategies to meet the challenges

7.1 Technological innovation and quality improvement of prefabricated buildings

Technological innovation is the key to meeting the challenges and improving the quality of prefabricated buildings. First of all, it is necessary to introduce advanced automation equipment and intelligent system in the process of component production to improve the production efficiency and quality control level. Secondly, through the introduction of BIM technology, the digital management of the construction process is realized, including the comprehensive monitoring and analysis of the construction progress, material use, quality inspection and other aspects, so as to improve the controllability of the construction quality. In addition, virtual reality (VR) and augmented reality (AR) technologies can also be used to simulate and train the assembly process to improve the operation skills and accuracy of construction personnel. The comprehensive application of these technological innovations can improve the quality level of prefabricated buildings, reduce construction risks, and meet the needs of users for high-quality buildings.

7.2 Project management strategy and efficiency improvement of prefabricated buildings

Project management strategy is an important means to improve the efficiency of prefabricated buildings. First of all, full planning and design should be carried out in the early stage of the project, including the optimization of the construction process, process standardization and resource allocation, to ensure the efficient implementation of the construction process. Secondly, the information management system is adopted to realize the real-time monitoring and analysis of the project progress, resource use and quality control, and to find out the problems in time and take corresponding measures to improve the construction team, carry out cooperative operation and team management, improve the communication and coordination ability, and reduce mistakes and delays. Finally, a sound risk management mechanism should be established, including the assessment and prevention measures of construction safety, quality risk and supply chain risk, to ensure the smooth progress of prefabricated building projects. Through the scientific and effective project management strategy, the construction efficiency of prefabricated buildings and the overall project operation effect can be improved, and better economic benefits and user satisfaction can be achieved.

8. Conclusion

As an innovative way of building, prefabricated building systems have great potential to improve quality and efficiency. Through the research of this paper, we deeply explore the impact of prefabricated buildings on the quality and efficiency of construction engineering, and look into its future development trend. While prefabricated building systems face some challenges, these challenges can be overcome and better results are achieved through technological innovation and the application of project management strategies. In the future, with the continuous progress of technology and the strengthening of international exchanges and cooperation, prefabricated buildings will become an important driving force for the transformation and upgrading and sustainable development of the construction industry. We believe that the development of prefabricated buildings will bring higher quality and more efficient construction solutions to the construction industry, and promote the sustainable development of cities and the improvement of people's quality of life.

References

[1] Tian Linqian. Research on carbon emission measurement and system dynamics simulation of prefabricated buildings [D]. Xi'an University of Technology, 2023.

[2] Xu Jianning. Research on the design of intelligent engineering management system of BIM technology [J]. Smart Buildings and Smart City, 2022, (11): 108-110.

[3] Gunawardena Tharaka, Mendis Priyan. Prefabricated Building Systems—Design and Construction [J]. Encyclopedia, 2022, 2(1).

[4] Xiao Yanwu, Bhola Jyoti. Design and optimization of prefabricated building system based on BIM technology [J]. International Journal of System Assurance Engineering and Management, 2021, 13 (Suppl 1).

[5] Baghdadi Abtin, Heristchian Mahmoud, Kloft Harald. Connections placement optimization approach toward new prefabricated building systems [J]. Engineering Structures, 2021, 233.

[6] Liu Yan. Research on engineering quality evaluation of regional prefabricated buildings based on system model [D]. Jilin University of Architecture, 2019.

[7] Satheeskumar Navaratnam, Tuan Ngo, Tharaka Gunawardena, David Henderson. Performance Review of Prefabricated Building Systems and Future Research in Australia [J]. Buildings, 2019, 9(2).

[8] Roy Griffith. Implementing Offsite Construction and Prefabricated Building Systems [J]. Design Cost Data, 2018, 62(3).

[9] Wesz Josana Gabriele Bolzan, Formoso Carlos Torres, Tzortzopoulos Patricia. Planning and controlling design in engineered-to-order prefabricated building systems [J]. Engineering, Construction and Architectural Management, 2018, 25(2).

[10] Gu Mingyan, Dong Lei, Li Xu. Research on the comprehensive application technology for the rapid construction of prefabricated buildings [J]. Real Estate World, 2020, (22): 53-55.